Estimate of the probable cost of restoring Aimarsapur Uddandiyankere Registered No. 511, Bowringpet Taluk.

Item of work	Quantity	Per	Rate	Cost
BUND.			Rs. a. p.	Rs.
1. Earthwork including watering and tamping ...	3,079	C.yd.		
2. Turfing	2,170	S.yd.		
3. Resetting old stone with new jelly ...	305	C.yd.		
4. New stone work	407	,,		
5. Preparing and fixing new grade stones including cutting figures and painting.	12	Each		
6. Do index stone do ...	12	,,		
7. Register No. stones	1	,,		
8. B. M. stones	2	,,		
9. Gauge stones	1	,,		
10. Removing prickly pears and jungle and cutting grips.	12	Grade		
Total Bund ..	...	...		
SLUICE.				
11. Earthwork excavation	76	C.yd.		
12. Earthwork refilling	83	,,		
13. Surki concrete	240	C.ft.		
14. Burnt brick in surki mortar	546	,,		
15. Burnt stone slabs 4″ to 6″ thick	265	,,		
16. Plastering with surki mortar	5·70	Sqr.		
17. Cast iron pipe of 5″ diameter	27	R.ft.		
18. Plug and rod with locking arrangements ...	1	No.		
19. Drilling holes on slabs	2	No.		
Total Sluice ..	...	...		
WASTE WEIR.				
20. Earthwork excavation	458	C.yd.		
21. Burnt brick in surki mortar	519	C.ft.		
22. Burnt stone slabs 6″ thick	242	Sq.ft.		
23. Plastering with surki mortar	5·61	Sqr.		
24. Rough stone work new	151	C.yd.		
25. Providing joggles	10	No.		
Total Waste Weir ...	...	...		
Grand Total ...	...	...		
Contingences ...	...	..		
Grand Total	...	...		

N. LAKSHMINARSIMHAIYA,
Executive Engineer.

MYSORE SPECIAL DIVISION.

No. *Dated 28th March* 1928.

Notice is hereby given that sealed tenders will be received at the Office of the Executive Engineer, Special Division, Mysore, upto 20th April 1928, till 2 P.M., for providing and fixing Wall Almirahs in the University Library Building, Mysore. An approximate quantities is given below. These quantities are not guaranteed. The work should be completed by the end of May 1928.

2. The plans, detailed estimate and conditions may be seen at the Executive Engineer's Office at Mysore between the hours of 11 A.M. and 5 P.M. on the working days.

3. Tenders should be submitted on printed forms which may be obtained from the Executive Engineer. The tenders should be accompanied by a statement in the form given below, showing the rates at which the different items specified will be executed :—

Description of work	Unit of work	Rate per unit	
		In words	In figures

4. Each tender must be accompanied by a deposit of rupees one-hundred and fifty (Rs. 150) in cash or Government Promissory Notes, State Loan Bands at market rates or in Savings Bank Pass Book of the tenderer having that amount at his credit on that date as earnest money, and be superscribed "Tender for providing and fixing Wall Almirahs in the University Library Building at Mysore" in default of which tenders will be rejected.

5. The final acceptance of the tender will rest with the Executive Engineer, Special Division, Mysore, who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

6. Within eight days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond, in default of which, his tender will be considered cancelled, and his earnest money will be forfeited.

7. The name of the successful competitor, whose tender has been accepted, will be posted on the Notice Board in the Executive Engineer's Office in due course. No enquiries regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders, the earnest money on rejected tenders will be returned.

9. No tender stating "percentage less than the lowest tender or as per estimated rates will be accepted.

10. Once the tender has been accepted no claim for any concessions or higher rates will be entertained.

11. The work to be executed as per D.P.W. Specification.

12. The decision of the Executive Engineer in all matters, regarding measurements, rates, etc., shall be final and legally binding.

Abstract estimate.

No.	Item of work	Quantity	Per	Rate
				Rs.
1	Teakwood wrought and put up	107·59	C.ft.	
2	Teakwood reepers 2"×1" including fitting and fixing with screws.	1,965	R.ft.	
3	Teakwood cornice 4" × 3"	77	,,	
4	Teakwood glazed ornamental shutters four fold with hinges locking arrangements, etc., complete.	924	S.ft.	
5	Wood oiling 2 coats mixed with varnish	27·92	Sqr.	
6	Polishing the glazed shutters with sprit and polish ...	9·24	,,	

V. V. KARVE,
Executive Engineer.

MISCELLANEOUS DEPARTMENTS.

OFFICE OF THE DIRECTOR OF INDUSTRIES AND COMMERCE IN MYSORE, BANGALORE.

Notice dated 14th March 1928.

A steam heated Jaggery boiling plant belonging to the department will be sold by public auction at Oorgahalli, on Monday the 16th April 1928, commencing from 9 A.M.

Conditions.

(i) The article will be sold to the highest bidder subject to the confirmation of the Director of Industries and Commerce.

(ii) The purchaser has to deposit at the close of the bid one-fourth the amount of the final bid and the balance will have to be paid within one month from the date of the confirmation of the sale and the article to be removed after the full payment is made.

(iii) Failure to pay the amount within the prescribed time will entail forfeiture of the deposit and the article will be resold and the original bidder will have no claim on the proceeds of the same.

C. RANGANATHA RAO SAHIB,
Director.